
London Road Play Area Masterplan



# ea Masterplan September 2018



DRIVE

CEPAR

30

35

40

5 10 15 20 25

0

SURFACE IS DEGRAPING & NOT

PRAINAGE ISSUE

HERE - FLOODS IN WINTER & WET

WEATHER

50 metres

45

London Road Play Area Masterplan September 2018



A LOT OF FENCING VISIBLE FROM

CEPAR ROAD ENTRANCES AND ALL

LOOKS A BIT TIREP

Mon

BOTH ENTRANCES HIPDEN















**Basket swing** 





Platform for slide with different challenges



Equipment such as basket swings, wide slides and large spinning disks can be used for just sitting and calmer play a well as being exciting and challenging . They can be shared by all ages and children with a wide range of abilities

## Shared sociable play





Spinning disk for sharing the fun



Wide slide for sliding together











## Low key, natural & playful landscape

The most low key, inexpensive interventions can often be the most playful. A playful landscape can be introduced throughout the whole space such as low mounds and shallow ditches (especially if there is occasional water e.g. in the winter), logs for balancing, fallen tree for climbing, boulders for climbing and balancing. These elements can also make sociable gathering spaces for everyone















Ball Court with open sides and seating so everyone can use the space

Shared space

Lots of seating is key to making a space more sociable, shareable and accessible. There should be plenty of seats with backs and armrests. Seats can also be informal and playable.

Having open sides to the ball court means spectators can watch more easily and that the court can be used by anyone.

Children with different abilities and of different ages should be able to play together and not segregated.

A good path network makes an open space more accessible to different abilities and ramped access to e.g. sand areas can be designed in.

### Paths

A well designed path network for direct routes through the space helps everyone access it. Surfacing can be light coloured, naturalistic and low key, such as self binding gravel. It should be accessible for wheeled vehicles and wide enough for multiple use



Thresholds New hard surfacing at entrances should complement new path surfacing and provide a 'threshold' on entering the park. Small element paving such as granite setts are on a human scale



Include seats with backs and armrests

**Picnic tables** 







## **Boundaries**





Timber post and rail fence with steel mesh provides an attractive alternative for the dog walking area. Curves are more appealing and create better spaces



Alternatives for anew steel fence for smartening up the Cedar Drive boundary





A stile would give access to the dog walking area - for retrieving balls?



## Planting

Wildflower meadows provide more interest and important contact with nature as well as being good for wildlife





Shrubs such as Dogwoods, Willows and Hazel can be robust and playable with all year round interest. Ornamental grasses are tough as well as providing a valuable sensory experience.



New tree planting of native trees to keep a continuity of trees in the space and provide shade and shelter in the more open areas



Low key annuals such as Pictorial Meadows at entrances for a cheerful welcome

The hedge along the London Road boundary is an asset providing a green screen from the road but needs management. There's an opportunity to employ local skills for traditional hedge laying which would improve the density and life of the hedge





### Cost Estimate

### Phase 1

1	Preliminaries - site safety, client requirements, protection etc.	£5,000	13	Preliminaries - site safety, client requirements, protection etc.
2	Double gate in oak or timber with self closing single leaf	£750	14	Main through path from London Road to Cedar Drive - self
3	Play tower with slide 1.5 metre height, 1 metre wide slide	£10,000		binding gravel with timber edge, 1.2 metres wide
	with steps and various ways to access / get down - firemans		15	Path to dog walking area
	pole, nets etc.		16	Timber post & wire fence to dog walking area
4	Timber frame basket swing	£6,000	17	Stile over post and rail fence
5	Spinning disk	£8,500	18	New railings to boundary with Cedar Drive
6	Sand areas including excavation and drainage	£10,000	19	New goal ends to ball court
7	Natural glacial boulders	£2,000	20	Fallen tree with net
8	Low mounding around sand area	£4,000	21	Low mound and ditches around fallen tree area
9	Ball court with tarmac surface re-using existing goal ends	£9,000	22	Glacial boulders
10	New trees	£3,750	23	Natural logs and trunks
11	New shrub and herbaceous planting	£1,925	24	Picnic tables
12	New turf to make good areas	£3,000	25	Seats and benches
	2	-	26	Bins
	Sub total Phase 1	£63,925	27	Bulb planting
	Contingency @ 15%	£9,589	28	Meadow sowing and instant wildflower meadow turf
	Total Phase 1	£73,514	29	Turf to make good mown grass areas
		273,314		

Phase 2

Sub total Phase 2 £74,650 *Contingency @ 15%* £11,197 Total Phase 1 £85,848

### NOTES

- Cost estimates exclusive of VAT
- Works phased to fit secured or available budgets

£600 £10,000 £7,150 £400 £8,500 £22,000 £5,000 £3,000 £3,000 £2,500 £1,000 £4,000 £2,500 £1,000 £3,000 £1,000

£5,000

