

Michelle Barron  
Attleborough Town Council  
Town Hall  
Queens Square  
Attleborough  
Norfolk  
NR17 2AF  
England

Date: Friday, 15 July 2022  
Quotation Ref: 56732

Dear Michelle

**To provide an extra over Option of a Zipwire for Attleborough Town Council.**



**Project Brief**

We have pleasure in submitting our proposal for an additional extra over Aerial Zipwire for inclusion in the quoted London Road Play Area Project.

We have included this as a separate quotation, as it was part of the potential wish list, but due to budget, the unit and installation, took his over the target amount, but I wanted to quote this as it is shown on the plans, and it may be that the budget can extend, or this could be looked at as a Phase 2/later stage project.

When choosing OLP to design, manufacture and install your new design you will benefit from the following;

- An in-house designing and manufacturing team who take your project ideas and come up with additions we believe will add to the **fun, challenge and enjoyment of the design.**
- All our standard timbers are pressure treated after cutting to size and prior to installation with an ACQ (an arsenic and chrome free preservative) treatment, this provides a timber product which will give **long life expectancy.** OLP guarantee our timber against timber decay for 15 years.

- All our structural timbers used within our equipment now incorporate tubular steel post feet, this omits any timber deterioration through contact with the ground and will ultimately extend the life of the product.
- OLP is proud to represent Ledon as their main UK distributor of steel and HDPE product ranges including springers, swings and multiplay units. Over the past 37 years Ledon has become synonymous with manufacturing high quality play products focusing on play value. For further information visit [www.ledonplay.com](http://www.ledonplay.com)
- An independent family owned company who have been designing, manufacturing and installing play solutions in Schools and Nurseries, Parks, Leisure Amenities & Local Authorities for **30 continuous years**.
- All the members of our installation and groundworks team are directly employed by OLP.

**Don't just take our word for it**, come and see for yourself. As we operate an open manufacturing environment, we would be more than happy for you to arrange a visit to our offices and workshop here in Cambridgeshire.

Finally, we are an **API** (Association of Play Industries) member, giving you complete faith, you have chosen the correct supplier. Benefits include a Professional Code of Conduct, Financially secure and strict compliance to all the relevant safety standards.

## Project Quotation No.: 56732

Friday, 15 July 2022

### Aerial Runway and Surfacing - Optional extra



Code	Product	Qty	Each	Value
PRO-500-193	MLF22 Aerial Runway - 25m complete with starting platform and runoff all manufactured from ACQ	1	5,300.00	£5,300.00

	treated safalog with post feet and stainless steel mechanism. <b>**WITH POST FEET**</b>			
SAFAGRASS011	To supply and install safagrass matting to follow existing undulations of grass / turfed area including grass stabilisation mesh per m2 tested to EN1177	27	46.00	£1,242.00
PRO-INST-30	Installation Assembly (30) into a soft dig with good access including concrete foundations.	1	2,000.00	£2,000.00
<b>Subtotal:</b>				<b>£8,542.00</b>

<b>Net Total</b>	£8,542.00
<b>VAT</b>	£1,708.40
<b>Gross Total</b>	<b>£10,250.40</b>

## Project Construction Information.

### Equipment Materials

#### Safalog™

		
Common Issues with Pine Round Logs	Safalog™ Split resistant domed play timbers	Treated to Hazard Class 4 15 Year Timber Guarantee

All our timber equipment is manufactured to the highest standard and uses our unique laminated **Safalog™** split resistant timbers with user friendly domed ends. The timber used is high quality, slow grown pine supplied from sustainable resources, this is then pressure treated using **an environmentally friendly wood protection** which will give an expected 15-year service life against timber decay. Once treated, our timber complies with BSEN335 Part 1, use class 4 in ground contact timber.

### Surfacing Materials

#### Safagrass Matting



Our environmentally friendly Safagrass Matting complies with the standards of EN1177 and is suitable for a critical fall height of up to 3m. Safagrass Matting is ideal for green field sites and will disappear from view once the grass has grown through. No costly baseworks are required and the Safagrass mats are suitable for all weather conditions and extreme temperatures.

## Guarantees

The quality control systems (ISO9001) in place at OLP enable us to monitor the whole manufacturing and installation processes from start to finish. They also give us the opportunity to give all our customers a comprehensive guarantee package that offers peace of mind:

The playground equipment you buy from us is of the highest standard and is covered by our extensive guarantees.

### Equipment

- Structural timbers: 15 Years
- Steelwork: 15 years
- Ropes & nets: 2 years
- Moving parts: 2 Years
- Installation: 2 Year (all installers are direct employees of the company – not subcontractors)

### Surfacing

- Wetpour: 5 Years
- Safagrass: 5 Years
- Synthetic grass: 5 Years
- Resin Bound Rubber Mulch: 5 Years

### Warranty coverage

- In order to be covered by our warranty the outdoor play equipment must have been installed by Online Playgrounds
- If parts fail due to the manufacturing process, replacements will be supplied free of charge.
- Structural timbers are guaranteed subject to the outer treatment envelope having not been damaged. Any timber parts covered under the warranty that need to be replaced due to failure will be supplied free of charge.

- Any HDPE parts covered under the warranty that need to be replaced due to failure will be supplied free of charge.
- Please note that the warranty does not cover general wear and tear or acts of vandalism, malicious damage, and acts of God
- Where Black Wetpour surfacing is installed, colour fastness cannot be guaranteed, and some colour leakage may occur

### Project Assumptions?

The following assumptions have been made regarding this quotation:

- Good access will be available to the site.
- Spoil from our excavations to be retained on site. **If spoil is to be removed from site, an additional £340.00 will be added to the final invoice.**
- **Are amenities available on site? If amenities are not available for our team to use, an additional £173.00 will be added to the final invoice.**
- Equipment to be installed into current turfed area.
- It is assumed that the current base is stable.

### Contract Terms and Conditions

- All the enclosed prices are subject to VAT at the standard rate.
- All equipment and surfacing complies with EN1176 and EN1177.
- All our equipment is installed with Critical Fall Heights (CFH) compliance to EN1176/ EN1177 /EN16630.
- Once the equipment and or the surfacing has been installed and handed over we take no responsibility for any damage through abuse / vandalism or acts of god that may occur.
- Our quotation is open for acceptance for **30 days** from the quotation date.
- All materials and guarantees are referred to in our product specification.
- Security fencing can be supplied and erected at extra cost if deemed necessary by the customer.
- We will accept NO responsibility for detecting services or I.T cables etc. These should be clearly marked by others before any installation work commences.
- Suspension bridges, Burma bridges, single ropes and access nets are designed for a maximum of 1 person crossing at any one time; however additional people can be waiting to cross on the timber structures.
- Layout drawings and plans to be agreed and signed by the customer prior to the product being manufactured if an order is placed.
- **Where wetpour is provided on a "supply only basis" and OLP have not constructed the subbase a charge of £1,100 + VAT maybe charged if the surfacing cannot be laid on the agreed day due to incomplete baseworks.**
- Ownership of goods remains the property of Fenland Leisure Products Ltd until invoice is paid in full.
- Please visit our website [www.onlineplaygrounds.co.uk](http://www.onlineplaygrounds.co.uk) to view our full terms and conditions.

### Payment and Delivery Terms

- **Trading Accounts** - Total invoice payable within 28 days of project completion
- **Schools / Local Authority** - Total invoice payable within 28 days of project completion



**Online Playgrounds**  
Fenland House, Padgetts Road,  
Christchurch, Wisbech,  
Cambridgeshire PE14 9PJ

**T:** +44 (0) 1354 638 359  
**E:** sales@onlineplaygrounds.co.uk

[www.onlineplaygrounds.co.uk](http://www.onlineplaygrounds.co.uk)

- **Pro-forma Account** – We can also accept payment by Bacs or any major payment card.

Delivery: **8-10 weeks** from official order subject to seasonal demand.

We trust the above quotation meets with your approval and look forward to receiving your further valued instructions in the near future. If in the meantime, you need any further information or changes making to this proposal please don't hesitate to contact me.

Yours Sincerely

Richard Taylor  
Sales Development & Key Accounts  
[richard.taylor@onlineplaygrounds.co.uk](mailto:richard.taylor@onlineplaygrounds.co.uk)