



ITEMS LIST

Toddler Equipment		
1. Cradle Swing		Ref:J474A
2. Wheelchair Roundabout		Ref:J2409A
3. Treefrog Springer		Ref:J985A
4. Tortoise Springer		Ref:J870A
5. Tic Tac Toe Play Panel		Ref:UKFITICTAC6
6. 3 in Row Game Play Panel		Ref:UKFIROW6
7. Tema Amazon Multiplay Unit		Ref:J2636A-M
8. Playhouse		Ref:J234A
9. Existing Dome Climber		

Junior Equipment		
10. Kanope Special Multiplay Unit		Ref:Z21-5633
11. Double Perch (Green Spring)		Ref:Z19-0825
12. Mini Rope Hammock Swing		Ref:J443A
13. Flat Swing		Ref:J472A

Ancillaries		
14. 44Lm of 1m High Bowtop Fencing Galvanised		Ref:UKN1000
15. 1m High Hydraulic Self Closing Gate Powdercoated Yellow		Ref:UKN1101
16. 1m High Combination Gate Powdercoated Yellow		Ref:UKN1113
17. Existing Maintenance Gate		
18. Existing Pedestrian Gate		

Safety Surfacing
Area to be surfaced with 167m² of Flecked Wetpour with graphics as shown at depths of:

167m ²	@ <1.2m
Colour breakdown:	
124.5m ²	@ Black/ Dark Green 50/50 Fleck Wetpour
11m ²	@ Standard green wetpour
6.5m ²	@ Beige wetpour
25m ²	@ Standard blue wetpour

To be laid over existing wetpour bases and new stone bases requiring 67m² of Excavation & MOT type 1 stone with 94Lm of chase cut into turf.

Junior Equipment to be surfaced with 162m² of EcoSmart Grassmat

Removals

- Cut removal of 2x swings, slide, 2x springers & 43Lm of fencing

Miscellaneous

- Preliminaries including site setup, site storage, delivery, unloading of equipment, site welfare, heras fencing & signage and skips.
- Post Installation Inspection has been included.
- Supply & Install Drainage to help reduce standing water under Flush Roundabout

Optional Extras

- Removal of 3x Existing Benches & 2x Bin.

18. 3x Chaumont Benches	Ref:RBA8
19. Waste Bin	Ref:RC01

25m² of 35mm thick SUDS-bond surfacing with gold aggregate. Including 43LM chase into surrounding turf. Requiring 25m² of Excavation and MOT type 1 stone.

Drainage for underneath the J2409A Roundabout has been included, this is to help prevent flooding but does not ensure that flooding will not occur.

Proposed Grassmat Safer surfacing is based on a fully established grass site (including a minimum of 150mm of good quality soil and turf).

Proposed Grassmat will follow the natural contours of the land.

Preliminaries have been included within your quotation, these equates to site setup, safety fencing, safety signage, welfare, offloading of equipment, storage & waste removal.

Fencing will be made up from standard straight lengths and installed faceted. If rounded fencing is required this will incur additional costs.

PRODUCT KEY	
	Wetpour
	Grassmat
	Existing Wetpour
	Existing Concrete Plinth
	Permeable Paving
	New Fencing
	Existing Fencing

London Road
Attleborough Town Council

DATE: 16/05/2022 REF: 2205.33732(LondonRoad_AttleboroughTC)

REV: - DB: JPS CB: TY

SCALE: 1:200 @ A3

